SANTA CLARA

mechanical **GATEWAY** & electrical details

5455 GREAT AMERICA PARKWAY

	DESCRIPTION	QTY	NOTES
HVAC	Cooling Towers Marley Crossflow Closed Loop	2	 Includes 6" Vertical Piping Loop to Ground Floor Serves 15 Water Source Heat Pumps Throughout Building 155 Tons Each
	Supplemental Cooling Liebert Computer Room Air Conditioning Units	31	Includes Intellislot Web CardsIncludes Low Sound PackageUnits Serve Lab, Server, UPS & IDF Rooms
	Supplemental Cooling Mitsubishi Fan Coil Units with Air Cooled Rooftop Condenser	6	Includes Washable FiltersIncludes Remote Control ThermostatUnits Serve Lab & IDF Rooms
ELECTRICAL	4000 AMP Building Service		
	Uninterruptible Power Supply (UPS) 500 KVA Emerson Liebert NX Series		Scalable to 600 KVA
	1600 AMP Panel Feeding 1st Floor Server Lab	1	• Includes Starline Busway with Bus Plug-in Boxes
	200 AMP Panel on 4th Floor Feeds Labs & IDF on 3rd and 4th Floors	1	
	400 AMP Panel on 5th Floor Feeds 5th Floor Labs and MDF	1	
GENERAL	Lab Type Spaces Throughout Building	10	 Approximately 6,000 Square Feet of Lab Space Approximately 2,200 AMPS Distributed to Labs Most Labs Include Supplemental Cooling and Generator Emergency Power
	Distributed Antenna System for Emergency Services Throughout Building	N/A	
	Basket Tray Low Voltage Wire Management System Installed Throughout Building	N/A	